

Photon Detector

XPM85112

10 μ m MCP-PMT

25 mm Square, 4x4 Anode

- Superior Magnetic Field Immunity
- Enhanced Timing Performance

miniPLANACON[®]




Applications

- ✓ Specialized Medical Imaging
- ✓ Cherenkov – RICH, TOF, TOP, DIRC
- ✓ High Energy Physics Detectors
- ✓ Homeland Security


Description	
Window	Synthetic Fused Silica
Photocathode	Bialkali
Multiplier structure	MCP chevron (2), 10 μ m pore, 60:1 L:D ratio
Anode structure	4x4 array, 5.8 / 6.4 mm (size / pitch)
Active area	25x25 mm
Package Dimensions	32mm x 32mm x 24mm

Photocathode characteristics	Min	Typ	Max	Unit
Spectral range:	200		650	nm
Peak Quantum Efficiency at 380 nm*	18	22		%
Operating Characteristics	Min	Typ	Max	Unit
Overall Voltage for 10 ⁵ Gain *		FIG	2800	V
Total anode dark current @ 10 ⁵ gain *		< 1	10	nA
Spatial Uniformity		< 1.5:1	2:1	
Rise time**		0.5		ns
Pulse width**		0.7		ns
Transit time spread (σ_{tts})**		< 35	50	ps
Maximum Magnetic Field Operation		2		T

Typical spectral response




Recommended Voltage Divider (not included)



CAUTION: POWER GROUND CONNECTION AND UNUSED ANODES MUST BE CONNECTED TO GROUND FOR SAFETY AND PROPER TUBE OPERATION

Typical gain curve



* Characteristic measured and recorded on the test ticket of each tube


** Characteristic for single photoelectrons at 405 nm.

Photon Detector


XPM85112

Outline (dimensions in mm)

XPM85112/A1



Internal Connection Schematic – XPM85112/A1 *



Limiting values	Min	Max	Unit
Cathode to MCP _{in} voltage		500	V
MCP _{in} to MCP _{out} voltage		2400	V
MCP _{out} to Anode voltage		500	V
Overall HV when using recommended voltage divider		2800	V
Total anode current under uniform illumination		2	μA
Ambient temperature:			
Operating Temperature	0	+50	°C
Storage Temperature (for extended periods)	-15	+50	°C

* Custom or unfurnished external connections are available upon request.

** Warning: Continuous operation at maximum ratings may result in shorter product life or unreliable performance.

The information furnished is believed to be accurate and reliable, but is not guaranteed and is subject to change without notice. No liability is assumed by PHOTONIS USA Pennsylvania, Inc. for its use. Performance data represents typical characteristics and not specifications as actual, individual product performance may vary. Customers should verify that they have the most current product information before placing orders, and should independently test and evaluate PHOTONIS products for their intended use.

No claims or warranties are made as to the application of PHOTONIS products or their suitability or fitness for any particular purpose. This document may not be reproduced, in whole or in part, without the prior written consent of PHOTONIS USA Pennsylvania, Inc.

PHOTONIS

PHOTONIS USA Pennsylvania, Inc. 1000 New Holland Avenue, Lancaster PA 17601
 T: +1 (717) 295 2704 or Toll Free US/Canada (800) 366 2875
 E: info@photonisusa.com W: www.photonisusa.com

Rev01-2014